



# DASH8 - 400 NORMAL CHECKLIST



1 = CM1 2 = CM2 P = PF N = PNF B = BOTH CMs

PREFLIGHT		
(* Through Flight; same Flight Crew)		
Gear Pins	removed	1
* Circuit Breakers	checked	B
* DC / AC panel	checked	1
Ice protection	all off /doors open	1
Ignition	norm	1
Pressurization	auto/clsd/set	1
* Fueling on light	out	1
* Fasten Belts	on	1
* Emergency lights	armed	1
Aircondition	auto / set	1
Bleeds	min/off	1
Recirc fan	as req'd	1
LDG gear alt lights	3 green	2
LDG gear alt doors	top&bottom clsd	1
Inhibit switch	normal	1
Flight/Taxi switch	taxi	1
Steering	off	1
Pitot static isol valve	norm	1
Hydraulic control panel	checked	1
* ED messages	checked	1
* Fuel quantity	checked	1
Fuel panel	checked	1
Autofeather	off	1
Alternate feather	norm	1
Control lock	on	1
Power & Cond. levers	disc / fuel off	1
EFIS sources	both norm	1
ARCDUs	both FMS	1
Anti skid	on / checked	2
FWD outflow valve	norm	2
Crew Oxygen	checked	2
* Altimeters	QNH _____ set	B

TAXI		
Cabin report	received	1
Flight controls	checked	2
Iceprotection	Level _____	2

Inflight Checklists on the  
  
Control Column

AFTER LANDING		
Radar	off	2
Transponder	as req'd	2
Flaps	zero	2
Control lock	on	2
Tank aux pumps	off	2
Yaw Damper	off	2
Bus tie	on	2
Ice protection	off	2
Approach & Flare lights	off	2
Anti collision	red	2
Bleeds	on / norm	2
Flight/taxi switch	taxi	2
<b>Overspeed governor</b>	<b>tested</b>	<b>1</b>
<b>(mondays after last flight of day only)</b>		

BEFORE START		
Parkbrake	set	1
Trims	set	1
Takeoff speeds	set	B
DC Voltage	checked	1
Door lights	out	1
Anti collision	red	1
Escape hatch	clsd	1

SHUTDOWN		
Parkbrake	set	1
Power / Cond. Levers	disc / fuel off	1
Stby Hyd & PTU	norm	1
Transponder	stby	1
Steering	off	1
External power / APU	on / checked	1
Taxi & Emergency lights	off	1
Anti collision	off	1
Fasten Belts	off	1
Bleeds	min / off	1

AFTER START		
Ext. Power / APU	disconnected / off	1
Bus Tie	off	1
Windshields	as req'd	1
Recirc fan & Bleeds	on / norm	1
ED messages	checked	1
.....		
Condition levers	max	1
Flaps	_____	B
Autofeather	select	1
Power rating	NTOP/Reduced _____%	B
Tank aux pumps	on	1
STBY Hyd & PTU	on / 7 up	1
#3 isol valve	tested	2
Deice pressure	checked	2
Rudder travel	checked	1
Steering	on	1

LEAVING		
Instrument & utility lights	off	B
APU	off	1
Anti skid	off	2
Engine bypass doors	clsd	1
Avionics	off	B
.....		
Recirc fan	off	2
Ext. Power	off	1
Batteries & Master & Bus tie	off	1
Dome light	off	1